

SCHEDULE OF QUANTITIES:

NAILANA VILLAGE WATER SUPPLY

CONTRACT No:INF-W06/2022/2023

SCHEDULE B: BULK SUPPLY AND NETWORK DISTRIBUTION WORKS

SECTION 4: ANCILLARY WATER SUPPLY WORKS

ITEM NUMBER	PAYMENT CLAUSE	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
SUB-TOTAL SCHEDULE B - SECTION 4 BROUGHT FORWARD:						
B.4		ANCILLARY WORKS: <i>(As specified in the Project Specifications.)</i>				
4.2.4		Allow a Provisional Sum for removing, cleaning and handing over to the Engineer existing Boreholes H11- 2768 & 1372 pump equipment.	Prov Sum	2.00	R 75 000.00	R 150 000.00
4.2.5		Supply and install precast concrete pump house as per DWS specifications, complete with heavy duty lockable steel access door for boreholes above.	No.	1.00		-
4.2.6		Provision for ESKOM Connection for items 4.2.2, 4.2.3 & 4.3.1	Prov.Sum	1.00	R 170 000.00	R 170 000.00
4.2.7		Overheads, charges and profit on item 4.2.4 & 4.2.6	%	320 000.00		-
4.3		Water Package Plant in Nailana Village:				
4.3.1		Installation of 140 KL/day Water Treatment Package Plant for Reverse Osmosis.	Prov.Sum	1.00	R 2 160 000.00	R 2 160 000.00
4.3.2		Overheads, charges and profit on item 4.2.1,42.4 & 4.3.1	%	2 160 000.00		-
4.3.3		Allow for formation of a reed bed for effluent discharge in 4.3.1 above	Prov.Sum	1.00	R 75 000.00	R 75 000.00
4.3.4		Overheads, charges and profit on item 4.3.3	%	75 000.00		-
4.4		Palisade Fencing				
4.4.1		Supply, delivery and installation of 2.4 m high concrete palisade fence with 4.5m wide steel sliding gate, all inclusive of area clearance, civil foundations and all details as per drawing NAIL-STD-09 &10	m	100.00		
TOTAL SCHEDULE B - SECTION 4 CARRIED TO SUMMARY:						